BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/OW/WORK_INDENT14543

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/07/2014-15, Date: 31.10.2014

Construction of Temprovery Immersion Tank for Lord Ganesha idols at Rachenahalli Lake Near Muneshwara Temple in Ward NO 06, Byatarayanaprua Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of B VENUGOPAL REDDY	
				In Figures	In Words
1	31.5	Earth work in surface excavation in Hard soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed etc., complete and as per the directions of	Cum	172.10	Rupees One Hundred Seventy Two and Ten Paise Only
2	185.25	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary soil not exceeding 1.5m. In depth with lead upto 50m. after breaking of clods etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	221.42	Rupees Two Hundred Twenty One and Forty Two Paise Only
3	185.25	Above 1.5 Mtrs Depth Add 25% Extra	Cum	276.78	Rupees Two Hundred Seventy Six and Seventy Eight Paise Only
4	1000	Providing Plastic Sheet etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	5.94	Rupees Five and Ninety Four Paise Only
5	187	Supply of water Through water Tank for filling Tank etc., complete and as per the directions of the Engineer-in-charge of the work	Each	346.50	Rupees Three Hundred Forty Six and Fifty Paise Only
6	30	Providing Stone dust to approach road and near immersion tank for levelling and to protect not to sliping Sl No. 50 P II Code 400 metal Component etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	198.00	Rupees One Hundred Ninety Eight Only
7	88	Hire charge of pumping water 3.5 KL/hr capacity Pump etc., complete and as per the directions of the Engineer-in-charge of the work	Hr	34.65	Rupees Thirty Four and Sixty Five Paise Only
8	132	Engaging unskilled heavy Mazdoor laboru for Guarding and for helping the public to immersion tank Ganesh Idols and to safe guard the public during the pooja Time etc., complete and as per the directions of the Engineer-in-charge of the work	Days	190.48	Rupees One Hundred Ninety and Forty Eight Paise Only
9	3410	Hire Charges for Two Tier Barricading with casurens poles at 2.50mtrs C/C vertically and 0.50 mtrs C/C Horizontaly with Necessary earth work and labour etc., complete and as per the directions of the Engineer-in-charge of the work	Rft	16.83	Rupees Sixteen and Eighty Three Paise Only
10	13200	Hire Charge for Shamiyana with Necessary Bambo Poles, Erection Charges Including transportation - (Size: 40ft x 30ft = 1200 sqft) etc., complete and as per the directions of the Engineer-in-charge of the work	Sft	2.97	Rupees Two and Ninety Seven Paise Only
11	550	Hire Charges for Shamiyana Side Wall of 8ft Hight (Size: 10x 15ft = 150 Rft) etc., complete and as per the directions of the Engineer-in-charge of the work	Rft	16.83	Rupees Sixteen and Eighty Three Paise Only
12	660	Hire Charge for Armless Plastic Chairs etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	3.96	Rupees Three and Ninety Six Paise Only
13	132	Hire Charge for Wooden Table of Size 6ft x 2ft etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	39.60	Rupees Thirty Nine and Sixty Paise Only

Executive Engineer
Byatarayanapura Division
Yalahanka Zone, B.B.M.P.
Bangalore-560092

14	3080	Hire Charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathedaluminium wire etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	8.91	Rupees Eight and Ninety One Paise Only
15	110	1321 Hire charge of 100 KVA Generator including operator, Fuel, transportation and Handling charges etc., complete and as per the directions of the Engineer-in-charge of the work	Hr	490.05	Rupees Four Hundred Ninety and Five Paise Only
16	154	Hire chargesfor Flood lighting arrangements for the stage and existing immersion Tank during night time etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	282.15	Rupees Two Hundred Eighty Two and Fifteen Paise Only
17	10	Hire charges compoment name 1087 Crane charges etc., complete and as per the directions of the Engineer-in-charge of the work	Day	3168.00	Rupees Three Thousand One Hundred Sixty Eight Only
18	370.5	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50mm, and lift upto 1.5m, including cost of all labour etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	59.88	Rupees Fifty Nine and Eighty Eight Paise Only

B. Venugopal Reddy

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92